# COMcheck Software Version 4.1.5.5

# **Envelope Compliance Certificate**

#### **Project Information**

Energy Code:

90.1 (2013) Standard

Project Title:

Taco Bell

Location:

Pontiac, Michigan

Climate Zone:

5a

Project Type:

**New Construction** 

Vertical Glazing / Wall Area:

11%

Performance Sim. Specs:

EnergyPlus 8.1.0.009 (EPW: USA\_MI\_Detroit.Metro.AP.725370\_TMY3.epw)

Construction Site: Walton Boulevard Pontiac, MI 48340 Owner/Agent:
Bob Grabowski
Dortch Enterprises, LLC
8487 Retreat Dr.
Grand Blanc, MI 48439
810-771-4500 ext 1018

bgrabowski@dortchenterprises.com

Designer/Contractor:
Greg Lautzenheiser
L+A Architects, Inc.
441 S. Livernois
Suite 265

Rochester Hills, MI 48307

248-524-4700

glautzenheiser@laarchitectsinc.co

m

#### **Building Area**

#### Floor Area

1-Dining: Cafeteria/Fast Food : Nonresidential 2241

#### **Envelope Assemblies**

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor <sub>(a)</sub>
Roof 1: Insulation Entirely Above Deck, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	2241		40.0	0.025	0.032
Floor 1: Slab-On-Grade:Unheated, Vertical 4 ft., [Bldg. Use 1 - Dining: Cafeteria/Fast Food] (b)	237		5.0	0.540	0.520
NORTH					
Exterior Wall 2: Wood-Framed, 16" o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	419	19.0	5.0	0.048	0.051
Window 2: Metal Frame:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.18, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	100			0.421	0.420
Door 3: Glass (> 50% glazing):Metal Frame, Entrance Door, Perf. Specs.: NFRC CPD-ID P-KAW-8754, SHGC 0.23, PF 0.18, VT 0.37, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	24			0.763	0.770
EAST					
Exterior Wall 4: Wood-Framed, 16" o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	1012	19.0	5.0	0.048	0.051
Window 3: Metal Frame:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.18, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	15			0.421	0.420
Window 4: Metal Frame:Operable, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.72, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	11			0.421	0.500

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page 1 of 11

Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor(a)
Window 7: Metal Frame with Thermal Break:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.72, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	46	144E)	500	0.421	0.420
Window 8: Metal Frame:Operable, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.72, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	11		***	0.421	0.500
Window 9: Metal Frame:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.72, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	13		200	0,421	0.420
SOUTH  Exterior Wall 6: Wood-Framed, 16" o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	419	19.0	5.0	0.048	0.051
WEST Exterior Wall 1: Wood-Framed, 16" o.c., [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	1012	19.0	5.0	0.048	0.051
Window 1: Metal Frame with Thermal Break:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.18, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	49	200		0.421	0.420
Window 6: Metal Frame with Thermal Break:Fixed, Perf. Specs.: NFRC CPD-ID P-KAW-6993, SHGC 0.37, PF 0.72, VT 0.66, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	27		<u>=41</u>	0.421	0.420
Door 2: Insulated Metal, Swinging, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	27	<u> </u>		0.410	0.500
Door 5: Glass (> 50% glazing):Metal Frame, Entrance Door, Perf. Specs.: NFRC CPD-ID P-KAW-8754, SHGC 0.23, PF 0.72, VT 0.37, [Bldg. Use 1 - Dining: Cafeteria/Fast Food]	24	Hee	•••	0.763	0.770

<sup>(</sup>a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.

## Envelope PASSES: Design 0.1% better than code

### **Envelope Compliance Statement**

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed envelope systems have been designed to meet the 90.1 (2013) Standard requirements in COMcheck Version 4.1.5.5 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Name - Title

Signature

8/18/2022

PRESIDENT, L+A ARCHITECTS

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page 2 of 11 Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

<sup>(</sup>b) Slab-On-Grade proposed and budget U-factors shown in table are F-factors.



# **COM***check* Software Version 4.1.5.5

# **Inspection Checklist**

Energy Code: 90.1 (2013) Standard

Requirements: 0.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
4.2.2, 5.4.3.1.1, 5.7 [PR1] <sup>1</sup>	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	□Complies □Does Not □Not Observable □Not Applicable	
4.2.2, 8.4.1.1, 8.4.1.2, 3.7 [PR6] <sup>2</sup>	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the electrical systems and equipment and document where exceptions are claimed. Feeder connectors sized in accordance with approved plans and branch circuits sized for maximum drop of 3%.	□Complies □Does Not □Not Observable □Not Applicable	

Additional Comments/Assumptions:

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title:

Taco Bell

Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page

Section # & Req.ID	Footing / Foundation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
4.2.4 [FO1] <sup>2</sup>	Installed below-grade wall insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R	R	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	See the Envelope Assemblies table for values.
4.2.4 [FO3] <sup>2</sup>	Installed slab-on-grade insulation R- R- Complies		See the Envelope Assemblies table for values.		
5.8.1.2 [FO4] <sup>2</sup>	Slab edge insulation installed per manufacturer's instructions.			Complies Does Not Not Observable Not Applicable	
5.5.3.5 [FO5] <sup>2</sup>	Slab edge insulation depth/length.	ft	ft	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	See the Envelope Assemblies table for values.
5.8.1.7 [FO6] <sup>1</sup>	3.1.7 Exterior insulation protected		☐Complies ☐Does Not ☐Not Observable ☐Not Applicable		
5.8.1.7.3 [FO7] <sup>1</sup>	Insulation in contact with the ground has <=0.3% water absorption rate per ASTM C272.			□Complies □Does Not □Not Observable □Not Applicable	7 7 8 7 9 9 1 9 1 9
6.4.4.1.5 [FO11] <sup>3</sup>	Bottom surface of floor structures incorporating radiant heating insulated to >=R-3.5.	tures R R □Complies		See the Envelope Assemblies table for values.	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
5.4.3.2 [FR1] <sup>3</sup>	Factory-built and site-assembled fenestration and doors are labeled or certified as meeting air leakage requirements.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
5.4.3.4 [FR4] <sup>3</sup>	Vestibules are installed where building entrances separate conditioned space from the exterior, and meet exterior envelope requirements. Doors have self-closing devices, and are >=7 ft apart (>= 16 ft apart for adjoinging floor area >= 40000 sq.ft.). Vestibule floor area <=7 50 sq.ft. or 2 percent of the adjoining conditioned floor area.			□Complies □Does Not □Not Observable □Not Applicable	
5.5.4.3a [FR8]¹	Vertical fenestration U-Factor.	U	U	☐Complies ☐Does Not ☐Not Observable	See the Envelope Assemblies table for values.
5.5.4.3b [FR9] <sup>1</sup>	Skylight fenestration U-Factor.	U	□Not Applicable □Complies □Does Not □Not Observable □Not Applicable		See the Envelope Assemblies table for values.
5.5.4.4.1 [FR10] <sup>1</sup>	Vertical fenestration SHGC value.	SHGC:	SHGC:	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.5.4.4.2 [FR11] <sup>1</sup>	Skylight SHGC value.	SHGC:	SHGC:	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.2.1, 5.8.2.3, 5.8.2.4, 5.8.2.5 [FR12] <sup>2</sup>	Fenestration products rated (U- factor, SHGC, and VT) in accordance with NFRC or energy code defaults are used.			Complies Does Not Not Observable Not Applicable	
5.8.2.2 [FR13] <sup>1</sup>	Fenestration and door products are labeled, or a signed and dated certificate listing the U-factor, SHGC, VT, and air leakage rate has been provided by the manufacturer.			Complies Does Not Not Observable Not Applicable	
	U-factor of opaque doors associated with the building thermal envelope meets requirements.	U Swinging Nonswinging	U Swinging  Nonswinging	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
	Continuous air barrier is wrapped, sealed, caulked, gasketed, and/or taped in an approved manner, except in semiheated spaces in climate zones 1-6.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
---	----------------------	---	------------------------	---	---------------------

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page 5 of 11 Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Taco Bell Report date: 08/18/22 Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
8.4.2 [EL10] <sup>2</sup>	At least 50% of all 125 volt 15- and 20-Amp receptacles are controlled by	□Complies □Does Not	
	an automatic control device.	□Not Observable □Not Applicable	

1						
	1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

Section	Inculation Incuration	Plans Verified	Field Verified	Committee	Comments/Accounts
# & Reg.ID	Insulation Inspection	Value	Value	Complies?	Comments/Assumptions
4.2.4 [IN2] <sup>1</sup>	Installed roof insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports. For some ceiling systems, verification may need to occur during Framing Inspection.	R Above deck Metal Attic	R Above deck Metal Attic	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.2, 5.8.1.3 [IN3]¹	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the ceiling slope is <= 3:12.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
4.2.4 [IN6] <sup>1</sup>	Installed above-grade wall insulation type and R-value Mass Does Not Consistent with insulation specifications reported in plans and COMcheck reports.		See the Envelope Assemblies table for values.		
5.8.1.2 [IN7] <sup>1</sup>	Above-grade wall insulation installed per manufacturer's instructions.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
4.2.4 [IN8] <sup>2</sup>	Installed floor insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R Mass Steel Wood	R Mass Steel Wood	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.1 [IN10] <sup>2</sup>	Building envelope insulation is labeled with R-value or insulation certificate has been provided listing R-value and other relevant data.			Complies Does Not Not Observable Not Applicable	
5.8.1.9 [IN18] <sup>2</sup>	Building envelope insulation extends over the full area of the component at the proposed rated R or U value.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
5.8.1.4 [IN11] <sup>2</sup>	Eaves are baffled to deflect air to above the insulation.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
5.8.1.5 [IN12] <sup>2</sup>	Insulation is installed in substantial contact with the inside surface separating conditioned space from unconditional space.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
[IN13] <sup>2</sup>	Recessed equipment installed in building envelope assemblies does not compress the adjacent insulation.			□Complies □Does Not □Not Observable □Not Applicable	
[IN15] <sup>2</sup>	Attics and mechanical rooms have insulation protected where adjacent to attic or equipment access.			□Complies □Does Not □Not Observable □Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Report date: 08/18/22 Taco Bell

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck 8 of 11

Section # & Req.ID	Insulation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
5.8.1.7.2 [IN16] <sup>2</sup>	Foundation vents do not interfere with insulation.			□Complies □Does Not □Not Observable □Not Applicable	
5.8.1.8 [IN17] <sup>3</sup>	Insulation intended to meet the roof insulation requirements cannot be installed on top of a suspended ceiling. Mark this requirement compliant if insulation is installed accordingly.			□Complies □Does Not □Not Observable □Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)	

Project Title:

Taco Bell

Report date: 08/18/22

Section # & Req.ID	Final Inspection	Compiles?	Comments/Assumptions
5.4.3.3 [FI1] <sup>1</sup>		□Complies □Does Not	
		□Not Observable	
		□Not Applicable	

L	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page 10 of 11 Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck

Project Title: Taco Bell Report date: 08/18/22

Data filename: C:\Users\rj-bu\Documents\Rich's Work\21017 - Taco Bell - Walton Blvd., Pontiac, MI\Constructio Page 11 of 11 Documents\COMcheck Files\Taco Bell - Pontiac, MI 081522.cck